

15-151-21414-00-50

To: 1 040195
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA
C E/2, SEC. 16, T 26 S, R 13 W/E
2640 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243
Operator: Commonwealth Petroleum Corporation
Name & Address P.O. Box 2458
Hutchinson, KS 67504

Lease Name Keller Well # A-1
County Pratt 149.73
Well Total Depth 4607 feet
Conductor Pipe: Size _____ feet
Casing Size 10 3/4 feet 253

Abandoned Oil Well Gas Well _____
Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated LEC 5-1988

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 29 Month: 11 Year: 1988

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4600' PBTD 4570' Perfs at 4530'

1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 29 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 75 psi and shut in 0 psi-well went on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2115' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 8 1988

INV. NO. 23255

Signed Stephen J. Pfeifer
(TECHNICIAN)