

To: 1 040581
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4

API NUMBER 15- 151-20,907-00-00 272
SW NW SE, SEC. 29, T. 26 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers Inc.
Name &
Address P.O. Box 251
Great Bend, KS 67530

1650 feet from S section line
2310 feet from E section line
Lease Name Mowbray Well # 2A
County Pratt 149.19
Well Total Depth 4529 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 4 Month: 8 Year: 19 92

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

work: 5 1/2" at 4529' w/225 sx cement, PBDT 4318', Perfs at 4290-98'
1st plug sand back to 4240' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 4 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 150 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2107.05' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
8-13-92
AUG 13 1992

INVOICED

DATE 8-20-92
OBSERVE THIS PLUGGING.

Signed Steve Pfeifer
(TECHNICIAN)

DATE 8-20-92
INV. NO. 35995