

To: **041285** 2-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

AP# NUMBER 15-Drilled 10/6/59 15-151-10801-0002
NW SE SE, SEC. 29, T 26 S, R 13 W/E
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3911
Operator: RAMA Operating Co., Inc.
Name & Address: P.O. Box 159
Stafford, KS 67578

Lease Name Mowbray Well # 2
County Pratt 140.08
Well Total Depth 4310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 856

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 2 p.m. Day: 12 Month: 2 Year: 19 98

Plugging proposal received from Monte Andrews
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 7" at 4268' w/225 sx cement, CIBP 4200', Perfs at 3970-74, 3990-96, 4021-26, 4100-04'
1st plug sand back to 3900' and dump 7 sx cement on top of sand through bailer,
2nd plug pump down 10 3/4" with 300 lbs. hulls, 10 sx gel, 70 sx cement, 15 sx gel, 100 lbs.
hulls, release 10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 12 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 7 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 70 sx cement, 15
sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE FEB 22 1998
INV. NO. 50116

FEB 18 1998
2-18-98
CONSERVATION DIVISION
KANSAS
Signed Stephen J. Pfeifer
(TECHNICIAN)