

1100047

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,584 - 00 - 00  
50' S & 100' W OF  
C W/2 NE NW SEC. 22, T 29 S, R 15 (W) X

TECHNICIAN'S PLUGGING REPORT

4570 feet from N/S section line  
3730 feet from N/E section line

Operator License # 5298

Lease Name Hogard Well # 1

Operator: Gould Oil, Inc.

County Pratt 159.67

Name & Address P. O. Box 8640

Well Total Depth 4913 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 1:00 am Day: 14 Month: March Year: 19 85

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 405-232-7834

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 850' with 50 sx cement

2nd plug at 425' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Blayne Wiley  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 am Day: 14 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, 2nd plug at 425' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
3-15-85  
MAR 15 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Blayne Wiley  
(TECHNICIAN)

DATE 4-4-85

INV. NO. 7538