

To: 1 060979  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
120' S of C  
NE NE NW, SEC. 23, T 29 S, R 15  
4830 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7435  
Operator: Jim's Well Service  
Name & Address: Box 362  
Chase, KS 67524

Lease Name "R.G." Sante Fe Well # 1  
County Pratt 157.63  
Well Total Depth 4850 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Jim's Well Service License Number 7435

Address Box 362, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 14 Month: 7 Year: 19 87

Plugging proposal received from Jim Gillespie

(company name) Jim's Well Service (phone) 316-938-2338

were: 5 1/2" at 4848' Perfs at 4554-66', Elevation 1966' GL

1st plug sand back to 4650' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 14 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2009' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-20-87

INV. NO. 17528  
7-14

RECEIVED  
JUL 16 1987  
7-16-87  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi (TECHNICIAN)