

1 060978

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
SE NW NW, SEC. 23, T. 29 S, R. 15 W/E
4290 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7435
Operator: Jim's Well Service
Name & Address: Box 362
Chase, KS 67524

Lease Name "RG" Santa Fe Well # 2
County Pratt 157.63
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jim's Well Service License Number 7435
Address Box 362, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 14 Month: 7 Year: 19 87

Plugging proposal received from Jim Gillespie

(company name) Jim's Well Service (phone) 316-938-2338

were: 5 1/2" at 4849' Perfs at 4704-26' Elevation 1956' GL

1st plug pump 2 sx hulls and 20 sx cement-stop at 4000',

2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 14 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

Maximum pressure 700psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2521' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging

JUL 16 1987

DATE 7-20-87

CONDUCTED BY Signed: Paul A. Luthi
Wichita, Kansas (TECHNICIAN)

INV. NO. 17527
7-14