

1 050544

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C N/2 N/2 NE, SEC. 23, T 29 S, R 15  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,609-00 *for*  
N/2 N/2 NE, SEC. 23, T 29 S, R 15

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

4950 feet from S section line  
1320 feet from E section line

Operator: VAC Petroleum Co.  
Name & Address: 333 N. Rock Road  
Suite 105  
Wichita KS 67206

Lease Name Howell Well # 1-23  
County Pratt 159.06  
Well Total Depth 4894 Arbuckle feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 337

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran drillin Co. License Number 5829

Address 453 S. Webb Road, Suite 110, Box 18611 Wichita KS 67207

Company to plug at: Hour: 8:00 am Day: 2 Month: June Year: 19 85

Plugging proposal received from Wayne Boughn

(company name) Aldabaran Drilling Co. (phone) 316-685-5372

ware: Keep hole full of good heavy drilling mud and spot all plugs through open ended  
drill pipe. First plug at 930' with 50 sacks of cement. 2nd plug at 360' with 40'  
sacks of cement. <sup>3rd</sup> plug at 40' build a solid bridge and fill hole with 10 sacks of  
cement. Use 60/40 pozmix 2%gel 3% cc for all the cement. Also circulate the rathole  
and the mouse hole with 10 sacks each. The anhydrite top was at 900'

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:00am Day: 2 Month: June Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of good heavy drilling mud and spotted all plugs  
through open ended drill pipe. 1st plug at 930' with 50 sacks of cement. 2nd plug at  
360' with 40 sacks of cement. 3rd plug at 40' built a solid bridge with 1sx of hulls  
and a 8 5/8" wiper plug and filled hole to surface with 10 sacks of cement. Circulated  
Rat hole and mouse hole with 10 sacks of cement each. Hallibrton pumped the 60/40  
pozmix 2%gel 3%cc cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-7-85  
JUN 07 1985

Remarks: (If additional description is necessary, use BACK of th CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (copy to be observed) observe this plugging.

DATE 6-18-85

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 8568