

4-020150

SEP 06 2000

9-6-00

CONSERVATION DIVISION
Wichita, Kansas

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-25,034-0000

S2 NE NE /4 SEC. 26, 11 S, 19 W
4280 feet from S section line
670 feet from E section line

Operator license# 5259

Lease: Denis Vine Well # 1

Operator: Mai Oil Operations, Inc.

County: Ellis 119.28

Address: P.O. Box 33
Russell, Kansas 67665 8/28

Well total depth 3670 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 244 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Drive - Sterling, Kansas 67579

Company to plug at: Hour: 3:00 P.M. Day: 28 Month: August Year: 2000

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: 316-278-2476

Were: Ordered out 270 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot off casing at 2418'.
Prod Perfs at 3627' - 3630'; 3615' - 3618'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour: 6:00 P.M., Day: 28 Month: August, Year: 2000

Actual plugging report: 8 5/8" set at 244' w/160 sxs. 5 1/2" set at 3667' w/800 sxs.
Sanded back to 3560' and topped with 5 sxs cement with dump bailer.
Shot casing off at 2418'.
Pulled casing to 2000' - tied onto and pumped 140 sxs with 300# hulls.
Pulled casing to 1473' - tied onto and spotted 50 sxs with 100# hulls.
Pulled casing to 850' - tied onto and spotted 30 sxs.
Pulled casing to 150' - tied onto and circulated cement.
Pulled casing out of hole.
Hole standing full of cement.

Remarks: Allied Cementing Company.
Condition of casing (in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug (in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2080 GL

I did / did not observe the plugging.

Jay Fisher
(agent)

INVOICE
DATE 9/8/00
NO. 2001060611

Form CP-273
MB