

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23650-00-00
Spot: CSWNENE Sec/Twnshp/Rge: 30-11S-18W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MCNEELEY B Well Number: 1
County: ELLIS Total Vertical Depth: 3715 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size feet: 8/20.74
Surface Casing: Size 8.625 feet: 223 125 SX CMT
Production: Size 5.5 feet: 3719 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/04/2002 1:30 PM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 290 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 700# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/04/2002 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2000' - 1400' - 800'.
Hooked onto 8 5/8" and pumped to pressure with 45 sxs.
Max. P.S.I. 700#. S.I.P. 300#.
Swaged on 5 1/2" - mixed and pumped 40 sxs with 400# hulls followed by 14 sxs gel.
Topped with 160 sxs cement and 300# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.

RECEIVED
KANSAS CORPORATION COMMISSION
APR - 9 2002
4-9-02
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

APR 08 2002

DATE 4-10-02

INV. NO. 2002061634

BAKER OIL WELL SVC
PLAINVILLE KS

30-11S-18W
SW NE NE

#1 MCNEELEY B

site: 9-3/4 N & 7-1/2 W OF CATHERINE KS city: ELLIS API 15-051-23650
 contr: RANGER DRILLING field: RIVERVIEW
 geol: JIM DILLIE
 Tr date 10/07/83 spd date 10/14/83 drlg comp 10/19/83 card issued 02/16/84 last revised 05/06/96

ELV: 2085 KB, 2080 GL DRLRS
 tops.....depth/datum
 ANH.....1391 + 694
 B/ANH.....1426 + 659
 RTD.....3715 -1630
 NO OTHER TOPS RPTD

IP status:
 OIL, ARB 3620-3654 OA, 11/20/83
 INFO REL: 5/6/96 - WAS TIGHT HOLE
 NOTE: INFO REL 11/1/84 - ADDED WELL INFO
 CSG: 8-5/8" 223 / 125 SX, 5-1/2" 3719 / 200 SX
 NO CORES OR DSTS
 MICT - CO, PF (ARB) 3620-3628, W / 4 SPF, AC 1000 GAL (15%), SWB DWN, SO, PF (ARB) 3650-3654, W / 4 SPF, AC 1000 GAL (15%), SWB DWN, GSO, SET 2-7/8" TBG AT 3650, NO PKR, POP, OIL WELL (POTENTIAL NOT RPTD), 11/20/83 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS

COPYRIGHT 1996
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS