

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04949-00-00
Spot: CSWNWSW Sec/Twnshp/Rge: 22-11S-18W
1650 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: DEAN Well Number: 3
County: ELLIS Total Vertical Depth: 3576 feet

Operator License No.: 5386
Operator Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 136
Production: Size 5.5 feet: 3516
Liner: Size _____ feet:

116.22

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2000 2:00 PM
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Rods & tubing parted in hole at 1450' - unable to recover casing - poor condition.
Fluid level 200'. T.D. 1450'.
Run tubing to T.O.F. and circulate hole with cement.
Ordered out 345 sxs 60/40 pozmix - 10% gel with 700# hulls.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/17/2000 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Unable to get below 1200'. Perforated at 1200' and 700'.
Ran tubing to 1180'. Allied Cement pumped 130 sxs 60/40 pozmix - 10% gel with 300# hulls. Cement circulated.
PTOH and squeezed 100 sxs with 100# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
Hooked up to 8 5/8" and pumped 10 sxs cement.
Max. P.S.I. 700#. S.I.P. 400#.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 2000
11-30-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks:

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12/1/00

TRAIL NO. 2001061047

Form CP-2/3

NOV 27 2000

H. H. BLAIR

3 DEAN

22-11-18W
SW NW SW

Contr. _____ ELLIS _____ County

E 1982 Comm. 4-18-48 Comp. 6-11-48 IP 235 BOPD PHY POT

Tops	Depth	Datum
ANK HEEB	1286 3166	+696
LANS	3212	-1230
CONG	3472	-1490
ARB	3514	-1532 ✓
T.D.	3526	✓

Casing
 10" 136 2000' 01H/2 HRS:
 5" 3516

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS