

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23651-00-00⁰⁰
Spot: CNWNENE Sec/Twnshp/Rge: 30-11S-18W
4950 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MCNEELEY B Well Number: 2
County: ELLIS Total Vertical Depth: 3720 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size _____ feet: \$120.90
Surface Casing: Size 8.625 feet: 205 125 SX CMT
Production: Size 5.5 feet: 3716 200 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2002 11:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 290 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 700# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/04/2002 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2000' - 1400' - 800'.
Hooked onto 8 5/8" and pumped to pressure with 25 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Swaged onto 5 1/2" - mixed and pumped 40 sxs cement with 450# hulls followed by 14 sxs gel.
Topped with 140 sxs cement with 250# hulls.
Max. P.S.I. 1000#. S.I.P. 700#.

RECEIVED
KANSAS CORPORATION COMMISSION
APR - 9 2002
4-9-02
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-10-02

INV. NO. 2002061634

APR 08 2002

BAKER OIL WELL SVC
PLAINVILLE KS 67663

30-11S-18W
NW NE NE

#2 MCNEELEY B

site: 10 N & 7-1/2 W OF CATHERINE KS city: ELLIS API 15-051-23651
contr: RANGER DRILLING field: RIVERVIEW
gsd: JIM DILLIE

lr date 10/07/83 spd date 10/21/83 drlg comp 10/27/83 card issued 02/16/84 last revised 05/06/96

ELV: 2088 KB, 2083 GL DRLRS
tops.....depth/datum
ANH.....1388 + 700
B/ANH.....1433 + 655
RTD.....3720 -1632
NO OTHER TOPS RPTD

IP status:
OIL, ARB 3616-3653 OA, 12/10/83
INFO REL: 5/6/96 - WAS TIGHT HOLE
NOTE: INFO REL 11/1/84 - ADDED WELL INFO
CSG: 8-5/8" 205 / 125 SX, 5-1/2" 3716 / 200 SX
NO CORES OR DSTS
MICT - CO, PF (ARB) 3616-3628, W / 2 SPF, AC 1000 GAL
(15%), SWB DWN, SO, PF (ARB) 3651-3653, W / 2 SPF,
AC 1000 GAL (15%), SWB DWN, SO, POP, OIL WELL
(POTENTIAL NOT RPTD), 12/10/83 - NO OTHER INFO
RELEASED BY OPERATOR OR ON KCC RECORDS
(WELL P & A 1/7/92, NO CSG RECOVERED)

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS