

1

DEC 5 1986

15-151-10734-00-00

To: 080575
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-05,215

SE SE NE, SEC. 6, T 26 S, R 13 W EX

2970 330 feet from S section line

330 990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name F. Smith Well # 6

Operator: Range Oil Company, Inc.

County Pratt 133.06

Name & Address 1120 KSB&T Bldg.,

Well Total Depth 4094 feet

125 N. Market

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 10 3/4 feet 596

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P.O. Box 206, Geneseo, KS 67444

Company to plug at: Hour: 11:15 a.m. Day: 5 Month: 12 Year: 1986

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6483

were: 7" at 4094' Perfs at 3910-14, 3856-64' PBDT 3970'

1st plug sand back to 3435' and dump 7 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 5 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3360' - well was already plugged at 3435'

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 10 3/4" wiper plug and pump 150 sx cement.

STATE CORPORATION COMMISSION

DEC 9 1986 12-9-86

CONSERVATION DIVISION
Maximum pressure 500 psi and shut with 300 psi.

Remarks: Recovered 1371' of 7" casing. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed J. A. [Signature]
(TECHNICIAN)

DATE 12-10-86

INV. NO. 15580

INVOICED