

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10733-00-00
Spot: NENWSE Sec/Twnshp/Rge: 6-26S-13W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SMITH FRED Well Number: 5
County: PRATT Total Vertical Depth: 4078 feet

Operator License No.: 5120
Operator Name: RANGE OIL COMPANY, INC.
Address: 1120 KSB&T BLDG
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 10.75 feet: 599
Production: Size 7 feet: 4077
Liner: Size feet: 132.54

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/19/2000 9:00:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: SAND BACK TO 3747' WITH 7 SX CMT. 1ST PLUG AT 750' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/19/2000 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 3797-3952. SAND TO 3719' AND 6 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 750' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION
11-1-2000
NOV 1 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1860' OF 7" CASING.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE 11/2/00 OCT 23 2000
INV. NO. 2001060926

Form CP-2/3