

1 040559

8-6

194-00-00

36 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21, 154
SW NE SW, SEC. 6, T. 26 S, R. 13 W/EX

TECHNICIAN'S PLUGGING REPORT

1650 feet from S section line

3630 feet from E section line

Operator License # 5893

Lease Name Henderson Well # 1-6

Operator: Pratt Well Service, Inc.

County Pratt 143.65

Name & Address P.O. Box 847

Well Total Depth 4420 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 413

Abandoned Oil Well X Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 8 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4420' w/200 sx cement, Perfs at 3937-41, 3806-08'

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 6 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3666' and put 2 sx cement on top of CIBP,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1421' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

observe this plugging.

UNWITNESSED
DATE 9-5-91
INV. NO. 32955

AUG 14 1991
8-14-91
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] (TECHNICIAN)