

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,421-00-00

N/2 SE SW Sec. 11, T 26 S, R 13 W/E

990 feet from ~~XX~~/S section line

1980 feet from W/~~E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Keller "F" Well # 5

Operator: F & M Oil Company, Inc.  
Name & 422 Union Center  
Address Wichita, KS 67202

County Pratt

Well Total Depth 4405 feet 143.17

Conductor Pipe: Size        feet       

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A        X       

Other well as hereinafter indicated       

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12:30 pm Day: 18 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Lyle Cason

(company name) Union Drilling (phone) 316-262-1872

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4400' with 30 sx cement

2nd plug at 1250' with 50 sx cement

3rd plug at 410' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, plug water well with 5 sx cement

Signed J. A. McJ  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 7:45 pm Day: 18 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4400' with 30 sx cement, 2nd plug at 1250' with

50 sx cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plug - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement. Plug water well with 5 sx cement.

Remarks: Use 50/50 Pozmix 2% gel 3% cc by Sun

RECEIVED  
STATE CORPORATION COMMISSION  
4-30-84  
APR 30 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / ~~did not~~) observe this plugging.

Signed J. A. McJ  
(TECHNICIAN)

INVOICED

DATE 4-30-84

INV. NO. 1299