

TO: "
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21473-00-06
Spot: W2W2SE Sec/Twnshp/Rge: 11-26S-13W
1320 feet from S Section Line, 2050 feet from E Section Line
Lease/Unit Name: KELLER G Well Number: 6-F
County: PRATT Total Vertical Depth: 4375 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S. WEBB RD., STE 100
WICHITA, KS 67207

Conductor Pipe: Size feet: 8142.19
Surface Casing: Size 8.625 feet: 324 WITH 250 SX CMT
Production: Size 4.5 feet: 4099 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/05/2001 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BOTTOM TO 3700' & 4 SX CMT. 1ST PLUG AT 800' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/05/2001 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4099'. PERFS AT 3882-88 & 3756-62'. SANDED BACK TO 3700' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2618' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
11-9-01
NOV 09 2001
KCC WICHITA

INVOICED

NOV 07 2001

DATE 11-9-01
INV. NO. 2002060926

Handwritten signature and initials