

1090251

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-157-21,451-00-00
S/2 S/2 SE, SEC. 32, T 29 S, R 15 W/EK
330 feet from ~~N~~ SE Corner of ~~W~~ section line
1320 feet from ~~W~~ SE Corner of ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: Berexco, Inc.
Name &
Address 970 Fourth Financial Center
Wichita, KS 67202

Lease Name Gillam Well # 1
County Pratt 158.76
Well Total Depth 4885 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 20 Month: November Year: 19 84

Plugging proposal received from Stan Benoit

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 960' with 50 sx cement

2nd plug at 450' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by R. Barbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:41 am Day: 20 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 450' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-21-84
NOV 21 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOLVED (did not) observe this plugging.

DATE 12-3-84

Signed R. Barbutton
(TECHNICIAN)

INV. NO. 5724
11-20