

1041312

TO: STATE CORPORATION COMMISSION

8-13

API NUMBER 15-151-22,100 - 00-00  
SW NE NW SEC. 32, T 29 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HOWELL WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PRATT 161.85

OPERATOR LICENSE # 30606 WELL TOTAL DEPTH 4980 FEET

OPERATOR: MURFIN DRILLING, CO PRODUCTION CSG: SIZE 4 1/2 " FEET 4994'

NAME AND ADDRESS 250 N WATER, SUITE 300 SURFACE CASING: SIZE 8 5/8" FEET 422'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING, CO LICENSE NUMBER 30606

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 9:15 AM DAY: 13 MONTH: 08 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATWRIGHT

(COMPANY NAME) MURFIN DRILLING (PHONE) 316-267-3241

WERE: PERFS AT 4746-50, 4756-66, & 4792-4808 PBSD AT 4932'

1ST PLUG SAND TO 4500' & PUT 4 SX CEMENT ON TOP OF SAND, BRIDGE THROUGH BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 950' WITH 50 SX CEMENT, 3RD PLUG AT 450' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 13 MONTH: 08 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4500' & PUT 4 SX CEMENT ON TOP OF SAND, BRIDGE THROUGH BAILER,

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 950' WITH 50 SX CEMENT, 3RD PLUG AT 450' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
KANSAS DRILLING COMMISSION  
998 MS 20 A 9 54

Rec'd  
8-20-98

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. 3525' OF 4 1/2" CASING RECOVERED  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (IND) DESERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

INVOICED  
DATE 8-21-98  
INV. NO. 31186