

1060137

TO: STATE CORPORATION COMMISSION 12-13 API NUMBER 15-151-22,171-00-00
SW S12 SE SE SEC. 33, T 29 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME GILLAM WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PRATT 153.69

OPERATOR LICENSE # 5004 WELL TOTAL DEPTH 4729 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE " FEET

NAME AND 125 N MARKET, SUITE 1075 SURFACE CASING: SIZE 8 5/8" FEET 281'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MALLARD JV INC LICENSE NUMBER 4958

ADDRESS P.O. BOX 1009 McPHERSON, KS 67460-1009

COMPANY TO PLUG AT: HOUR: 11:30 PM DAY: 13 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM CAROL

(COMPANY NAME) MALLARD JV INC (PHONE) 316-241-4640

WERE:

1ST PLUG AT 825' WITH 50 SX CEMENT, 2ND PLUG AT 300' WITH 40 SX CEMENT,

3RD PLUG AT 40' WITH 10 SX CEMENT,

4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 13 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 825' WITH 50 SX CEMENT, 2ND PLUG AT 300' WITH 40 SX CEMENT,

3RD PLUG AT 40' WITH 10 SX CEMENT,

4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier
(TECHNICIAN) FORM CP-2/3

DEC 30 1998
60498