

To: 1 010008
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,512
C NE SE, SEC. 36, T 29 S, R 15 W EX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255
Operator: McGuinness Oil Co.
Name & Address: 1026 Union Center
Wichita, KS 67202

Lease Name Howell Well # 1
County Pratt 150.80
Well Total Depth 4640 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 pm Day: 8 Month: July Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4646' PBD 4250' Perfs at 4202-4207

1st plug sand back to 4150' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15 pm Day: 8 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 650 psi and shut in 100 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 2636 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED
DATE 7-24-85
INV. NO. 9097

RECEIVED
STATE CORPORATION COMMISSION
7-22-85
JMH 22 1985
CONSERVATION DIVISION
Wichita, Kansas