

~~NO~~
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964
1-2-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Co. & George Grenyo

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Griffith Well No. # 1

Location C NW SW NW Sec. 11 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4050

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson Oil Co.

Address: 412 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 8:30PM Day 31st Month December Year 1963

The Above well was plugged as follows:

416' of 8 5/8" surface pipe, cemented with 220 sacks. Fluid level was up in hole. 1st cementing plug and 1/2 sack hulls was pushed to 400', cemented with 30 sacks, through the drill pipe. Hole was filled with mud to 40', 2nd cementing plug, bridged with hulls, cemented with 12 sacks to base cellar. Rat hole bridged and cemented with 3 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/3/64
INV. NO. 8392-W

Signed: Archie Elving
Well Plugging Supervisor