

15,151,10713.00.00

GP

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORTS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

AUG 21 1967
8-21-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company
Complete Address 1860 Lincoln St., Denver, Colorado 80203
Lease Name Frisbie Well No. # 1
Location C SW NE SE Sec. 4 Twp. 26 Rge. 13 (E) (W) W
County Pratt Total Depth 4850'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Comstock Pipe Pulling, Inc.
Address Stafford, Kansas License No. 490
Operation Completed: Hour 11:00 A.M. Day 18th Month August Year 1967

The above well was plugged as follows:
795' of 8 5/8" surface pipe, cement circulated. 4397' of 5 1/2" long string,
cemented with 200 sacks. This is an open hole. Bottom plug was pushed to
3800', sand from 3800' to 3700', and cemented with 20 sacks, with cement
from 3700' to 3540', through the dump bailer. 2704' of 5 1/2" long string was
recovered from the hole. Bridge plug was pushed in fluid to 300', bridge plug
and rock bridge from 300' to 290'. 6 sacks of cement was mixed in a barrel
and put on plug at 290', through the dump bailer, and let set over-night.
Next day hole was bailed dry, and 19 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED.

Signed: Audie Elving
Well Plugging Supervisor

DATE 8-21-67
INV. NO. 6169-W