

15.151-10716-00.00

Form CP-3
Rev. 6-26-62

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name S. F. Chance Well No. # 3

Location NE SE SW Sec. 4 Twp. 26 Rge. 13 (E) W

County Pratt Total Depth 4334'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 10:00AM Day 31st Month August Year 1967

The Above well was plugged as follows:

831' of 8 5/8" surface pipe, cemented with 475 sacks. 4334' of 5 1/2" long
string, cemented with 200 sacks. Plug back T.D. 4008'. Top perforation
3850'. Bottom of the hole was sanded to 3800', and cemented with 20 sacks,
with cement from 3800' to 3640'. 2192' of 5 1/2" long string was recovered
from the hole. Fluid in the hole was at 340', bridge plug and rock bridge
from 340' to 330', and cemented with 25 sacks, with cement from 330' to
155'. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/6/67

INV. NO. 6267-W

Rec'd
9-6-67