

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1967
9-6-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name S. F. Chance Well No. # 2

Location SE SW SE Sec. 4 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4456'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford Kansas License No. 490

Operation Completed: Hour 12:00PM Day 28th Month August Year 1967

The Above well was plugged as follows:

820' of 8 5/8" surface pipe, cemented with 475 sacks. 4456' of 5 1/2" long string,
cemented with 200 sacks. Plug back T.D. 3873'. Top perforation 3860'. Bottom of
the hole was sanded to 3825', and cemented with 20 sacks, through the dump bailer,
with cement from 3825' to 3665'. 2128' of 5 1/2" long string was recovered from the
hole. Fluid level in the hole was at 340', bridge plug and rock bridge from 340'
330', and cemented with 25 sacks, with cement from 330' to 255'. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with
cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED
DATE 9/6/67
INV. NO. 6266-W