

15-151-10718-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*TC*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Gertrude Dodson Well No. # 2

Location SE NE SW Sec. 4 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4373'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 1:30PM Day 14th Month Sept. Year 1967

The Above well was plugged as follows:

833' of 8 5/8" surface pipe, cemented with 475 sacks. 4373' of 5 1/2" long string,  
cemented with 200 sacks. Plug back T.D. 3998'. Top perforation 3737'. Bottom of  
the hole was sanded to 3700', and cemented with 20 sacks, through the dump bailer,  
with cement from 3700' to 3540'. 1620' of 5 1/2" long string was recovered from the  
hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from  
300' to 290'. 6 sacks of cement with 8% Calcium Chloride was mixed in a barrel,  
and put on plug at 290', through the dump bailer, and let set for 2 hours. Hole  
was bailed dry, and 19 sacks of cement was added to the plug, Hole was filled with  
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement  
from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

STATE CORPORATION COMMISSION

Signed: Audie Elving  
Well Plugging Supervisor

DATE 9/15/67 SEP 15 1967  
6345-4 9-15-67

INV. NO. 6345-4 CONSERVATION DIVISION  
Wichita, Kansas