

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1975
12-4-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Halliburton Oil Producing Co

Complete Address 117 Cameron Bldg Oklahoma City, OK

Lease Name Belden Unit Well No. 1

Location SW/NW/SE Sec. 4 Twp. 26 Rge. 13 (E) (W)

County Pratt Total Depth 4040

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 624

Operation Completed: Hour 11:00 AM Day 3 Month 12 Year 1975

The above well was plugged as follows:

331 ft 8 5/8 surface cemented with 225 sacks. 3920 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 3750 ft. Sand to 3725 ft, 4 sacks
cement with bailer. Pulled 3108 ft 4 1/2. Pump 2 sacks hulls, 10 sacks
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell B. Burton*
Well Plugging Supervisor

DATE 12-04-75

INV. NO. 2347-W