

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1967
8-16-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

Operator's Full Name Skelly Oil Company
Complete Address 1860 Lincoln St., Denver, Colorado 80203
Lease Name J. B. Chance Well No. # 1
Location SW NW SE Sec. 4 Twp. 26 Rge. 13 (E) (W) W
County Pratt Total Depth 4351'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Comstock Pipe Pulling, Inc.
Address Stafford, Kansas License No. 490
Operation Completed: Hour 8:30 A.M. Day 14th Month August Year 1967

The above well was plugged as follows:

460' of 8 5/8" surface pipe, cemented with 250 sacks. 4343' of 5 1/2" long string, cemented with 200 sacks. Plug back T.D. 4008'. Top perforation 3811'.
Bottom of the hole was sanded to 3800', and cemented with 20 sacks, through the dump bailer, with cement from 3800' to 3640'. 2746' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from 300' to 290'. 4 sacks of cement was mixed in a barrel and put on plug at 290', through the dump bailer, and let set over week-end. Hole was bailed dry, and 21 sacks of cement was added to the plug, with cement from 290 to 215'. Hole was filled with mud to 40', rock bridge from 40' to 30' and cemented with 10 sacks, with cement from 30' to the base of the cellar.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 8/16/67
INV. NO. 6149-W