

15.151-00103-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

*A*  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 19 1967  
9-19-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Roy J. Kipp Well No. # 1

Location SW Cor. of Lot 4 Sec. 4 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 3950'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 2:30PM Day 18th Month Sept. Year 1967

The Above well was plugged as follows:

420' of 8 5/8" surface pipe, cemented with 250 sacks. 3950' of 5 1/2" long string,  
cemented with 200 sacks. Plug back T.D. 3907'. Top perforation 3800'. Bottom of  
the hole was sanded to 3750', and cemented with 20 sacks, through the dump bailer,  
with cement from 3750' to 3590'. 2319' of 5 1/2" long string was recovered from the  
hole. Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from 300  
to 290'. 3 sacks of cement with 8% Calcium Chloride was mixed in a barrel, and put  
on plug at 290', through the dump bailer, and let set for 2 hours. Hole was bailed  
dry, and 22 sacks of cement was added to the plug, with cement from 290' to 215'.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10  
sacks, with cement from 30' to the base of the cellar.  
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Clewing  
Well Plugging Supervisor

DATE 9/19/67

INV. NO. 6361-W