

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1967

9-8-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado

Lease Name S. F. Chance Well No. # 4

Location NW SE SE Sec. 4 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4389'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 1:30PM Day 5th Month Sept. Year 1967

The Above well was plugged as follows:

795' of 8 5/8" surface pipe, cemented with 475 sacks. 4389' of 5 1/2" long
string, cemented with 200 sacks. Plug back T.D. 4025'. Top perforation
3869'. Bottom of the hole was sanded to 3825', and cemented with 20 sacks,
through the dump bailer, with cement from 3825' to 3665'. 2618' of 5 1/2"
long string was recovered from the hole. Fluid level in the hole was at
300', bridge plug and rock bridge from 300' to 290', and cemented with
25 sacks, with cement from 290' to 215'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from
30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Arlie Elving
Well Plugging Supervisor

INVOICED

DATE 9/8/67
INV. NO. 6285-W