

9

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1967
8-24-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address 1860 Lincoln St., Denver, Colorado 80203

Lease Name S. F. Chance Well No. # 1

Location NW SW SE Sec. 4 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4383'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Comstock Pipe Pulling, Inc.

Address Stafford, Kansas License No. 490

Operation Completed: Hour 2:30 P.M. Day 23rd Month August Year 1967

The above well was plugged as follows:

435' of 8 5/8" surface pipe, cemented with 350 sacks. 4383' of 5 1/2" long string
cemented with 200 sacks. Plug back T.D. 4001'. Top perforation 3850'. Bottom
of the hole was sanded to 3800', and cemented with 20 sacks, through the dump
bailer, with cement from 3800' to 3640'. 2628' of 5 1/2" long string was recover-
ed from the hole. Bridge plug was pushed in fluid to 300', bridge plug and roc-
k bridge from 300' to 290'. 6 sacks of cement with 8% Calcium Chloride was
mixed in a barrel, and put on plug at 290', through the dump bailer, and let
set for 3 hours. Hole was bailed dry and 19 sacks of cement was added to the
plug, with cement from 290' to 215'. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to
I hereby certify that the above well was plugged as herein stated.
the base of the cellar.

Signed: Audrey Elwing
Well Plugging Supervisor

INVOICED

DATE 8-24-67
INV. NO. 6196-W