

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1964
10-19-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Sept 30 - 64

Dear Sir:

Mr. Pully of Forbes Casing Pulling Incorporated has this date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Graybol
~~Pratt~~ Oil Corporation

Complete Address: 2200 National Bank of Tulsa, OKLAHOMA

Lease Name: Howell Well No. #2

Location: C-SW-SE Sec. 31 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4661 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

322 feet of 8 5/8 inch surface pipe cemented with 230 sacks cement.

4600 feet of 4 1/2 inch long string cemented with 150 sacks. Plug back to

4561, top perforated. 4544 feet sand to 4520 feet cemented with 3 sacks.

Mud to 250 feet, 10 feet Rock Bridge cemented with 25 sacks mud to 40 feet;

10 feet Rock Bridge cemented with 10 sacks cement to base of cellar.

2420 feet of 4 1/2 inch pipe pulled.

Very truly yours,

Conservation Division Agent