

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1964
5-27-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. C. E. Richardson of Amerada Petroleum Corp. has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name: Eubank Well No. # 1

Location: C NW SW Sec. 32 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4705 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

320' of 9 5/8" surface pipe, cemented with 250 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 30 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 15 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent