

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-73  
MAR 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herrin of H-30 Drlg Inc has this

date requested permission to plug the following described well:

Mr. Herrin guarantees payment of the plugging fee.

Operator's full Name: Hershberger Exploration Inc

Complete Address: Suite 230 200 W Douglas Wichita, KS

Lease Name: Cooper Well No. 1

Location: A/ SE/SE/SW Sec. 33 Twp. 29s Rge. 14 (E)(W) W

County: Pratt Total Depth 4588 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Herrin was instructed to plug the well as follows:

790 ft 8 5/8 surface cemented with 600 sacks. Pump 50

sacks cement to 750 ft. Mud to 50 ft, plug, 1/2 sack hulls,

25 sacks cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Co Great Bend, KS

Very truly yours,

[Signature]  
Conservation Division Agent