

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 18 August, 19 58, authorized the following plugging operation:

Operator's Full Name: Twin Drilling Co.Complete Address: 1005 Central Bldg, Wichita, Kans.Lease Name: Toland "D" Well No. 1Location: NE NE SW Sec. 7 Twp. 26 Rge. 13 (E) (W) WCounty: Pratt Total Depth: 4910Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Sand to 3920' and dump five sack cement with dump bailer. Pull
pipe until free and circulate mud from rotary pit. Heavy mud to
220'. Set rock bridge and place 20 sack cement on bridge. Heavy
mud to 35'. Rock bridge and cement to base of cellar.

Very truly yours,

Signed [Signature]
 Conservation Division Agent

Rec'd
 8-29-58