

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 2 1964
 1-2-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this
 date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co. & George Grenyo

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Griffith Well No. # 1

Location: C NW SW NW Sec. 11 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4050 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

416' of 8 5/8" surface pipe, cemented with 220 sacks.
Fill hole with mud to 400', 1st cementing plug, bridge with
hulls, cement with 30 sacks. Fill hole with mud to 40',
2nd cementing plug, bridge with hulls, cement with 10 sacks
to base cellar. Bridge and cement rat hole with 2 sacks

Very truly yours,

Archie Elving
 Conservation Division Agent