

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1965  
11-15-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil & Walters Drilling Company

Complete Address: 1505 Wichita Plaza, Wichita, Kansas

Lease Name: Wiltshire Well No. # 1

Location: C SW SW Sec. 32 Twp. 29 Rge. 15 (E) (W) W

County Pratt Total Depth 4937' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

248' of 8 5/8" surface pipe, cement circulated with 200 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent