

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

June 27, 1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this
 date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Home Stake Production Company

Complete Address: Box 68, Burrton, Kansas 67020

Lease Name: Pitts Well No. W-29

Location: NE NW NW Sec. 15 Twp. 24 Rge. 4 (E) (W) X

County: Reno Total Depth 3376' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3340' and cement with 3 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 30 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 15 sacks cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 1 1968

CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

[Signature]
 Conservation Division Agent