



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8-18-76
AUG 18 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Co has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris Drlg Co Et Al

Complete Address: Box 334 Eldorado, KS

Lease Name: Minks Well No. 1

Location: SW/NE/NW Sec. 32 Twp. 24 S Rge. 11 (E) (W) W

County: Stafford Total Depth 3890 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

326 ft 8 5/8 surface cemented with 250 sacks. Pump plug,

35 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 5 sacks cement in

rat hole.

Pumped by Allied Cementing Great Bend, KS

Very truly yours,

[Signature]
Conservation Division Agent