



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

September 12, 1964

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

SEP 16 1964
 9-16-64
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. C. A. Richtor of Helmerich & Payne, Inc. has this

date requested permission to plug the following described well:

Mr. Richtor guarantees payment of the plugging fee.

Operator's full Name: Helmerich & Payne, Inc.

Complete Address: Box 558, Garden City, Kansas

Lease Name: Strandberg Well No. 1


Location: C SE SE SW Sec. 24 Twp. 23 Rge. 5 (E) (W) X

County Reno Total Depth 3904' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richtor was instructed to plug the well as follows:

Fill hole with mud to 730'. Push plug and 1/4 sack hulls to 730' and
cement hole with 20 sacks through drill pipe. Fill hole with mud
to 240'. Push plug and 1/4 sack hulls to 240' and cement hole with
20 sacks through drill pipe. Fill hole with mud to 40'. Push plug
and 1/2 sack hulls to 40' and cap hole with 10 sacks. Bridge rathole,
and cement with 2 sacks.

Very truly yours,

 Conservation Division Agent