



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 10, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1969
CONSERVATION DIVISION
Wichita, Kansas

8-14-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cecil Priar of Henry Wofford Drlg., Co. has this date requested permission to plug the following described well:

Mr. Priar guarantees payment of the plugging fee.

Operator's full Name: Woco, Inc.

Complete Address: 1016 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name: Gillmore "A" Well No. 1

Location: SE SE SW Sec. 26 Twp. 23 Rge. 5 (E)(W) X

County: Reno Total Depth 3895' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Priar was instructed to plug the well as follows:

Fill hole with mud. Push plug to 600' and cement hole with 25 sacks
cement pumped through drill pipe at 600'. Pump 25 sacks cement through
drill pipe at 200'. Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William D. Loren
Conservation Division Agent