



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

September 28, 1980

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT - 3 1980  
10-3-80  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Dick Davis of H-30 Drilling, Inc. has  
date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: National Oil Company

Complete Address: Suite 800, 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Brawner Well No. 1

Location: NE SW SE Sec. 26 Twp. 23 Rge. 5 (E) (W)

County: Reno Total Depth 3860' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Davis was instructed to plug the well as follows:

8 5/8" - 337' - 275 sacks. Fill hole with mud. Pump 50 sacks  
50-50 Pozmix w/2% gel added through drill pipe at 450'. Fill  
hole with mud to 40'. Push plug and 1/2 sack balls to  
40' and cap hole with 10 sacks cement.  
Cement rat hole with 5 sacks.

Very truly yours,

Phillip R. Dick  
Conservation Division Agent