



15-155-20610-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

September 5, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1979
9-17-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Kenneth Dahlberg of Texas Oil and Gas Corp has this date requested permission to plug the following described well:

Mr. Dahlberg guarantees payment of the plugging fee.

Operator's full Name: Texas Oil and Gas Corporation

Complete Address: Suite 300-200 W. Douglas, Wichita, Kansas 67202

Lease Name: Gillmore Well No. 1

Location: 330 E56-630 FWL-SW/4 Sec. 27 Twp. 23 Rge. 5 (W) (X)

County: Reno Total Depth 3935' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dahlberg was instructed to plug the well as follows:

8 7/8" - 239.55' set @ 245' - 250 sacks circ. Hole filled with mud.
Pump 50 sacks cement through drill pipe at 300' -
(50-50 pozmix w/4% gel added). Hole filled with mud to 40'.
Push Plug and 1/2 sack hulls to 40' and cap hole with 10
Sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent