

State of Kansas



FORM CP-2

15-155-20809-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

July 17, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Dick Davis of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Holt Oil & Gas Corporation

Complete Address: 8150 N. Central Expwy., Suite 1255, Dallas, Texas

Lease Name: Holt-Hempstid Well No. 1

Location: SE SW NE Sec. 35 Twp. 23 Rge. 5 ~~(E)~~ (W)

County: Reno Total Depth: 3910'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Davis was instructed to plug the well as follows:

8-5/8"-287'-175 sacks circ. Circulate and fill hole with mud. Pump

50 sacks cement through drill pipe at 520'. Pump 40 sacks cement through

drill pipe at 280'. Fill hole with mud to 40'. Push plug and 1/2 sack

hulls to 40' and cap hole with 10 sacks cement. Cement rathole with

10 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1981
7-23-81
CONSERVATION DIVISION
Wichita, Kansas