

15-55-19166-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Operator's Full Name Home Stake Production CompanyComplete Address: Box 68 Burrton, Kansas 67020Lease Name Pitts Well No. # 0-13Location App. C NW NW Sec. 15 Twp. 24 Rge. 4 (B) (W)County Reno Total Depth 3378'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling Co. Inc.Address: Chase, Kansas License No. # 624Operation Completed: Hour 830 PM Day 8 Month 8 Year 68

The Above well was plugged as follows:

10 3/4"-328'-Circulated w/cement. 5 1/2"-3345'-Cemented. Sand hole to 3325'.5 Sax. cement 3325' to 3275' Mud 3275' to 310'. Bridge 310' to 300'.35 Sax. cement 300' to 225'. Mud 225' to 40'. Bridge 40' to 30'.15 Sax. cement 30' to 0. Pulled 1431'-5 1/2"-pipe.

RECEIVED

STATE CORPORATION COMMISSION

AUG 12 1968 8-12-68

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed:

Well Plugging Supervisor

INVOICED

DATE

8/12/68

INV. NO.

8249-W