

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1964
4-29-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 321 W. Douglas, Wichita, Kansas

Lease Name McComb Well No. # 1

Location SW SW NW Sec. 24 Twp. 24 Rge. 11 (E) (W)W

County Stafford Total Depth 3812

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Morgan Well Plugging Service

Address: 102 West 18th St., Hutchinson, Kansas License No. 43

Operation Completed: Hour 12:30PM Day 28th Month April Year 1964

The Above well was plugged as follows:

270' of 10 3/4" surface pipe, cemented with 185 sacks. 3792' of 7" long
string, cemented with 200 sacks. Plug back to 3808'. Bottom of hole was
sanded to 3785', and cemented with 6 sacks. Fluid level was up in hole.
Plug was pushed to 250', with 10' of rock bridge. 5 sacks of cement was
mixed in barrel and put on plug through dump bailer, and let set for 2
days. Hole bailed down and 25 sacks of cement was added to plug. Hole
was filled with mud to 40', with 10' of rock bridge, and cemented with
15 sacks to base cellar. 1800' of 7" long string was recovered from the
hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/22/64
INV. NO. 9000-W