


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Pratt County, Sec. 33 Twp. 29S Rge. 14 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE 1/4  
Lease Owner Bulldog Pipe & Supply  
Lease Name Shriver Well No. 1  
Office Address 309 Mayo Building Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-16 1969  
Plugging completed 3-26 1969  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4560 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10	335	None
				5 1/2	None	3912

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Sanded to 4500'. Dumped 5 sacks of cement. Rigged up unit.  
Working pipe.  
Working pipe. Shot pipe at 3900'. Mud came in at 2500'.  
Circulating. Spotted 50 bbl of oil.  
Working pipe. Pulling pipe.  
Plugging well. Set rock bridge at 300'. Dumped 35 sacks of cement. Mud hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of March, 1969

My commission expires May 27, 1969  
(Notary Signature)  
Notary Public.

Well File  
HMS  
C-2-16

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

RECEIVED

CHAMPLIN OIL & REFINING CO.

FEB 25 1959

WICHITA, KANSAS

PAUL N. SHRIVER #1.  
SE SE SE SECTION 33-29-14W  
PRATT COUNTY, KANSAS

COMMENCED 1-23-59  
COMPLETED 2-14-59

DEPTH		FORMATION	REMARKS:
FROM	TO		
0	40	SURFACE CLAY	
40	191	SAND	
191	335	SAND, RED BED & SHALE	RAN 335' OF 10 3/4" CASING CEMENTED WITH 200 BAGS CEMENT.
335	725	RED BED	Heebner 3835
725	1260	RED BED, SAND & SHALE	Toronto 3858
1260	1910	SHALE & SHELLS	Douglas 3894
1910	2070	LIME SHALE & SHELLS	Lansing 4004
2070	2160	LIME & SHALE	B/Ks. City 4404
2160	2540	LIME	Marmaton 4415
2540	2830	LIME & SHALE	Viola 4502
2830	2965	SHALE & SHELLS	Simpson 4533
2965	3130	SHALE	Simp. sd. 4549
3130	3220	SHALE & SHELLS	REED 4561
3220	3495	SHALE & LIME	
3495	3800	LIME	
3800	3867	LIME & SHALE	DST #1 4504-4530/2 hrs.
3867	3880	LIME	GTS/20", TSTM
3880	4000	SANDY SHALE	Rec. 100' HOCM, 450' SIMO
4000	4054	LIME & SHALE	FP: 79-172
4054	4440	LIME	SIP: 1580/30" - 1565/60"
4440	4465	LIME & SHALE	
4465	4510	LIME, SHALE & CHERT	DST #2 4550-61/2 hrs.
4510	4530	LIME	GTS/8", G/228 MCF/10", 214 MCF/15", 139 MCF/20"
4530	4540	SHALE & CHERT	TSTM/30". Rec: 1005' Gassy Oil, 1515' SW, FP; 27
4540	4561	CHERT, SHALE & SAND	995, SIP 1265/30" - 1240/60"
4561	TD		RAN 4561' OF 5 1/2" CASING CEMENTED WITH 100 BAGS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1960  
CONSERVATION DIVISION  
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE PAUL N. SHRIVER #1 WELL.

*E. E. Hall*

STATE OF KANSAS )

COUNTY OF SEDGWICK )

SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 20TH DAY OF FEBRUARY, 1959, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES

September 13, 1962 *Catherine LaRue*

NOTARY PUBLIC