

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt

County. Sec. 16 Twp. 26 Rge. 13 (E) W (W)

Location as "NE/CNW&SW" or footage from lines NE NE NE

Lease Owner Lee Phillips Oil Co.

Lease Name ASHER Well No. 1

Office Address 1407 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 5 19 56

Application for plugging filed April 5 19 56

Application for plugging approved April 5 (verbally) 19 56

Plugging commenced April 5 ~~XXXXXX~~ 19 56

Plugging completed April 5 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 1506 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	820	8 5/8"	820'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from total depth to 300' with 20 sacks of cement pumped through drill pipe to this point - filled with heavy mud to 35' with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Co.
Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
Box 184, Great Bend, Kansas (Address)
SUBSCRIBED AND SWORN to before me this 7 day of April 19 56

My commission expires 1-20-58

Mary E. Van Pelt
Notary Public.
APR 24 1956
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 16 T 26 R 13 W
BOOK PAGE 51 LINE 34

Driller's Log

Company: Lee Phillips Oil Co.

Farm: Asher No. 1

NE NE NE Section 16-26-13W
Pratt County, Kansas

Commenced: March 21, 1956

Completed: April 5, 1956

0 - 90	Sand and clay	3640 - 3809	Shale and lime
90 - 135	Clay	3809 - 4087	Lime
135 - 675	Red bed	4087 - 4120	Lime and shale
675 - 815	Sand and shale	4120 - 4178	Lime, shale, chert
815 - 840	Anhydrite	4178 - 4231	Lime
840 - 1370	Shale	4231 - 4263	Lime and chert
1370 - 1580	Shale and shells	4263 - 4290	Shale and lime
1580 - 2700	Lime and shale	4290 - 4309	Lime
2700 - 2935	Shale and lime	4309 - 4355	Lime and chert
2935 - 3115	Lime	4355 - 4388	Chert and lime
3115 - 3235	Shale and lime	4388 - 4397	Lime and shale
3235 - 3276	Lime	4397 - 4424	Sand and lime
3276 - 3317	Shale and lime	4424 - 4458	Lime and chert
3317 - 3430	Lime	4458 - 4490	Shale and sand
3430 - 3640	Lime and shale	4490 - 4506	Lime
			Total Depth

Set 820' of 8 5/8" surface pipe. Cemented with 300 sacks of posmix and 250 sacks of common cement. Cement circulated.

Tops: Anhydrite 815
Arbuckle 4490

Ran Electric Log

Dry, plugged and abandoned.

Affidavit: State of Kansas SS:
County of Barton

I Allan Harms of Harms-Burt Drilling Company

being first duly sworn on oath state that I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Signed Allan Harms

Subscribed and sworn to before me this 7 day of April, 1956.

Comm. Exp. 1-20-58

Mary E. Van Pelt
Notary Public

PLUGGING
FILE SEC 16-26-13W
BOOK PAGE 51 LINE 34

APR 14 1956