

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20,907-00-00

LEASE NAME Mowbray

WELL NUMBER 2A

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 29 TWP. 26 RGE. 13 XX) or (N)

COUNTY Pratt

Date Well Completed NA

Plugging Commenced 8-4-92

Plugging Completed 2:00 PM

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Great Bend Casing Pullers, Inc.

ADDRESS P.O. Box 251, Great Bend, Kansas 67530

PHONE # (316) 793-9711 OPERATORS LICENSE NO. 4635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-4-92 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation NA Depth to Top 4290 Bottom 4298 T.D. 4529

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	301	0
				5 1/2	4529	2107

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each. Bottom plug: Sanded to 4240 & bailed 5 sx Cement.

Top plug: Pumped 300 lbs Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lbs Hulls, 8 5/8 Wiper plug, 100 sx 60/40 6% Gel. 150 maximum pressure & 100 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Bend Casing Pullers, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein and the log of the above-described well as filed, the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 5 day of August, 19 92



My Commission Expires: 4-30-96

Anna K. Burke  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
OBSERVATION DIVISION  
Wichita, Kansas

Recd  
8-6-92

Form C  
Revised 05