

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt

County. Sec. 29 Twp. 26 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Strata Drilling, Inc.

Lease Name Mowbray Well No. 1

Office Address P. O. Box 355, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-16 19 61

Application for plugging filed 10-16 19 61

Application for plugging approved 10-16 19 61

Plugging commenced 10-16 19 61

Plugging completed 10-16 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LaCamp

Producing formation Depth to top Bottom Total Depth of Well 4545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	846'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole Plugged as follows: Plugged at 400' with 20 sacks cement, 1/4 sack hulls and mud to 35'; plugged with 8 sacks of cement 1/4 sack hulls. 2 sacks of cement in rathole. Job completed at 3:00 A. M. 10-16-61.

RECEIVED  
STATE CORPORATION COMMISSION  
10-18-61  
OCT 18 1961

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Charles W. Steincamp (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
P. O. Box 355 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 61

My commission expires December 14, 1961

Elaine H. Taylor  
Elaine H. Taylor Notary Public.

D R I L L E R S   L O G

#1 Mowbray

CASING RECORD: 846' of new 8- 5/8" surface cas- ing	COMPANY: Strata Drilling, Inc.	DESCRIPTION: NW NW SW Section 29-26-13W Pratt County, Kansas
TOTAL DEPTH: 4545'	CONTRACTOR: Strata Drilling, Inc.	
	COMMENCED: September 29, 1961	
	COMPLETED: October 16, 1961	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	50	Ran 846' of new 8-5/8" surface casing; set and cemented at 846' with 250 sacks of regular cement, 5% gel and 2% C. C.; 150 sacks of regular cement, 2% gel and 2% C. C. Plug down at 7:00 P. M. 9-30-1961.
Sand	50	165	
Shale	165	540	
Red Bed	540	770	
Shale	770	855	
Anhydrite	855	865	
Red Bed, Shale & Shells	865	1555	
Shale & Lime	1555	2735	
Shale	2735	2740	
Lime & Shale	2740	3817	
Lime	3817	4300	
Lime & Chert	4300	4418	
Lime	4418	4428	
Shale & Sand	4428	4460	
Lime	4460	4465	
Shale & Sand	4465	4490	
Shale, Sand & Lime	4490	4545	
Total Depth 4545'			

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 18 1961  
CONSERVATION DIVISION  
Wichita, Kansas

Ran Log.  
D. & A.  
Plugged at 400' with 20 sacks of cement, 1/4 sack of hulls and mud to 35'; plugged with 8 sacks of cement and 1/4 sack of hulls. 2 sacks of cement in rathole. Job completed at 3:00 A. M. 10-16-1961.

STATE OF KANSAS }  
COUNTY OF BARTON } ss.


I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.  
*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 16th day of October, 1961.

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

My Commission Expires:  
December 14, 1961



10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64

10-15-64