

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 29 Twp. 29 Rge. 15 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Aylward Drilling Company et al
Lease Name Kerr Well No. 1
Office Address 813 1st National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 2 19 57
Application for plugging filed August 2 19 57
Application for plugging approved August 2 19 57
Plugging commenced August 2 19 57
Plugging completed August 2 19 57
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 5005 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 5005' to 200'; set Halliburton plug with 1/2 sack hulls and 20 sacks of cement from 200' to 140'; heavy mud from 140' to 35'; Halliburton plug with 1/2 sack hulls at 35' and cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company
Address 813 1st National Bank Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
J. A. Aylward

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Aylward
813 1st Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of August 1957

Paul W. Hesse

My commission expires December 11, 1957

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1957
8-13-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 29 R 15 W
BOOK PAGE 34 LINE 11

KERR #1

Casing Records:
8 5/8" - 186'

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Location: NE NE SW
Sec. 29-29-15W
Pratt County
Kansas
Elevations: 2040 RB

Commenced: July 15, 1957
Completed: August 2, 1957

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	95	Set 8 5/8" surface pipe @ 186' w/175 sacks cement
Shale & shells	95	200	
Redbed	200	290	Geological Tops:
Red Rock & redbed	290	500	
Red Rock & shale	500	880	Topeka 3551
Red Rock & gravel	880	993	Heebner Shale 3972
Red Rock & shale	993	1040	Douglas Shale 4009
Salt	1040	1190	Lansing 4137
Shale & lime shelves	1190	1890	Base Kans. City 4495
Shale & lime	1890	2125	Mississippian 4648
Lime & shale	2125	2325	Vinland chert 4817
Mostly lime - some shale	2325	2410	Simpson Shale 4860
Lime	2410	2500	Arbuckle 4955
Lime w/shale	2500	2630	RTD 5005
Lime & shale	2630	2815	
Shale w/lime	2815	2920	
Shale, very little lime	2920	3050	
Shale	3050	3195	DST 4650-80 Open 11 min. No blow.
Shale w/lime	3195	3330	Rec. 130# mud. ISIP 175#/25 min.
Shale	3330	3540	Packer leaked.
Shale w/lime	3540	3667	
Lime & shale	3667	3893	DST 4803-15 Open 30 min.
Sandy lime & shale	3893	3980	No blow. Rec. 5# mud.
Sand & lime	3980	4064	FP 20#-20#. ISIP 35#/20 min.
Lime & shale	4064	4125	FBHP 465#/20 min.
Lime	4125	4244	
Lime & shale	4244	4283	DST 4640-90 - Straddle test
Lime	4283	4350	Open 1 hr. Weak blow for 17 min.
Lime w/chert	4350	4411	Rec. 5# mud. FP 30#-40#
Lime	4411	4482	ISIP 0#/30 min., FBHP 65#/30 min.
Lime w/shale	4482	4517	
Lime & shale	4517	4595	
Lime w/shale	4595	4648	
Lime, chert & chat	4648	4680	
Lime & chert	4680	4691	
Lime & shale	4691	4717	
Chert & lime	4717	4759	
Lime w/shale	4759	4808	
Cherty lime	4808	4815	
Chert	4815	4832	
Chert & lime	4832	4859	
Cherty lime & shale	4859	4891	
Sand & shale	4891	4929	
Sand & lime w/shale	4929	4957	
Lime	4957	5005 T.D.	D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles J. Roberts

Subscribed and sworn to before me this 8th day of August, 1957.

Paul W. Kessel

My commission expires December 11, 1957

PLUGGING			
FILE	SEC 29	T. 29	R. 15W
BOOK	PAGE 34	LINE	11

Notary Public
STATE CORPORATE COMMISSION

AUG 13 1957

CONSERVATION DIVISION
Wichita, Kansas